

GNM Instrument Schedule (updated Jan 30/09)

Unit	Channel	Type	Name	Notes
1	n/a	Projector	n/a	Provided By Mermaid
2	1	Fresnal	Side	16' off centre
3	4	Fresnal	Back	8' off centre
4	5	Fresnal	Back	On centre
5	6	Fresnal	Back	8' off centre
6	2	Fresnal	Side	16' off centre
7	15	Blacklight	--	Provided By Mermaid
8	7	Birdie	Foot	Provided By Mermaid
9	15	Blacklight	--	Provided By Mermaid
10	7	Birdie	Foot	Provided By Mermaid
11	15	Blacklight	--	Provided By Mermaid
12	7	Birdie	Foot	Provided By Mermaid
13	15	Blacklight	--	Provided By Mermaid
14	8	S4 36degree	Front SR	
15	9	S4 36degree	Front CR	
16	10	S4 36degree	Front SR	
17	11	S4 36degree	Front SL	
18	12	S4 36degree	Front CL	
19	13	S4 36degree	Front SL	
20	14	Doll House	Practical	Practical 60w bulb

Unit	Channel	Type	Name	Notes
	n/a	Projector	n/a	Provided By Mermaid
	1	Fresnal w/ barn door OR source 4	High Side	16' off centre SR
	2	Fresnal w/ barn door OR source 4	High Side	16' off centre SL
	4	Fresnal	Back	8' off centre SR
	5	Fresnal	Back	On Centre
	6	Fresnal	Back	8' off centre SL
	7	Birdies (3 units)	Frontlight	Provided by Mermaid (if required)
	8	S4 36degree	Front SR	FOH apron wash
	9	S4 36degree	Front CR	FOH apron wash
	10	S4 36degree	Front SR	FOH apron wash
	11	S4 36degree	Front SL	FOH apron wash
	12	S4 36degree	Front CL	FOH apron wash
	13	S4 36degree	Front SL	FOH apron wash
	14	Doll House	Practical	Practical 60w bulb: dimmable
	15	Blacklight (4 units)	Blacklight	Provided by Mermaid: non dim

	16	Table Lamp	Practical	Practical 15 w bulb: non dim
--	----	------------	-----------	------------------------------

Please note the following:

- ⇒ all instruments are NO COLOUR
- ⇒ we are able to adapt to your house plot
- ⇒ our onstage lx pipe should be 14'0 from the plaster line OR 17'0 from the back wall depending on the size of your venue.
- ⇒ Contact stage management for details